

Project Info



02 / 12 / 2010



CC5 bulk rolls



180sqm



2 linear layers



Malkerns, Swaziland



Concrete Canvas SA



Crop irrigating canal required upgrading during peak irrigation season. Water flow was dammed briefly to allow re-shaping of the existing earth profile and installation of CC5. Hydration was conducted under flow conditions meaning re-commissioning of the canal took place much earlier than previously anticipated. The CC5 was installed in under 2 hours.

